Bill of Materials

Design: PSA-4113PA-BRVLMNYF-CHARLIE

Date: 1/17/2025

Category	Quantity	Material Cost (USD)	Labor Cost (USD)	Material Cost	Labor Cost
Structures	223	-	-	-	-
Equipment	175	-	-	-	-
Routes	32699.01 ft	-	-	-	-
Conduits	23948.05 ft	-	-	-	-
Cables	49916.40 ft	-	-	-	-
Total		-	-	-	-

Structures

Туре	Specification	FRC	Unit Cost	Quantity	Material	Cost (USD)	Labor	Cost (USD)	Material	Cost L	abor Cost
Cabinet	BJCNDL576-100ST	85C	-	1		-		-		-	-
UUB	HH10X15X12	85C	-	12		-		-		-	-
UUB	HH10X15X12	845C	-	29		-		-		-	-
UUB	HH17x30x24	85C	-	12		-		-		-	-
UUB	HH30X48	85C	-	24		-		-		-	-
Wall Box	Wall box	-	-	145		-		-		-	-
						_		_		_	_

Equipment

Туре	Specification	FRC	Unit Cost	Quantity	Material Cost (USD)	Labor Cost (USD)	Material Cost	Labor Cost
Fiber Panel	PFP Dist Pnl 288	85C	-	2	-	-	-	-
Fiber Panel	PFP Feeder Pnl 48	85C	-	2	-	-	-	-
Fiber Terminal	EVOLV12100RAW	85C	-	5	-	-	-	-
Fiber Terminal	EVOLV12200RAW	85C	-	1	-	-	-	-
Fiber Terminal	EVOLV12300RAW	85C	-	1	-	-	-	-
Fiber Terminal	EVOLV12400RAW	85C	-	3	-	-	-	-
Fiber Terminal	EVOLV12500RAW	85C	-	1	-	-	-	-
Fiber Terminal	EVOLV121000RAW	85C	-	3	-	-	-	-
ONT	Generic ONT	-	-	145	-	-	-	-
Splice Closure	FOSC450D6	85C	-	10	-	-	-	-
Splitter	1X64 Splitter	85C	-	2	-	-	-	-
					-	-	-	-

Routes

Туре	Specification FRC	Quantity	Material Cost (USD) Labor Cost (USD) Material Cost	Labor Cost
Route (Underground)		32699.01 ft	-		-
			-		_

Conduits

Туре	Specification	FRC	Quantity	Material Cost (USD) Labor Cos	st (USD) Materi	al Cost Labo	Cost
Conduit	2" SDR-11 Smooth-Wall Orange	85C	18844.94 ft	-	-	-	-
Conduit	IDUCT 1.25 W TAPE	845C	5103.10 ft	-	-	-	-
				-	-	_	-

Cables

Туре	Specification	FRC	Quantity	Material Cost (USD)	Labor Cost	(USD) Materi	al Cost Labor	Cost
Fiber Cable	5B92MT-048	85C	4057.15 ft	-		-	-	-
Fiber Cable	5B92MT-072	85C	4799.20 ft	-		-	-	-
Fiber Cable	5B92MT-144	85C	7820.26 ft	-		-	-	-
Fiber Cable	12F Tail	85C	3377.29 ft	-		-	-	-
Fiber Cable	96F-PFP TAIL	85C	42.63 ft	-		-	-	-
Fiber Cable	288-PFP TAIL	85C	235.26 ft	-		-	-	-
Fiber Cable	Dielectric 432f	85C	1474.08 ft	-		-	-	-
Fiber Cable	FIBERDROP1	845C	28110.52 ft	-		-	-	-
				-		-	-	_