#### Bill of Materials

# Design: PSA-1517PA-BRVLMNYF-CHARLIE

Date: 11/2/2025

Category	Quantity	Material Cost (USD) Labo	or Cost (USD) Mater	ial Cost Labor Co	ost
Structures	330	-	-	-	-
Equipment	248	-	-	-	-
Routes	40744,97 ft	-	-	-	-
Conduits	26379,18 ft	-	-	-	-
Cables	69814,63 ft	-	-	-	-
Total		-	-	-	-

#### Structures

Туре	Specification	FRC	Unit Cost	Quantity	Material	Cost (USD)	Labor	Cost (USD)	Material	Cost	Labor	Cost
Cabinet	BJCNDL576-100ST	85C	-	1		-		-		-		-
UUB	HH10X15X12	85C	-	23		-		-		-		-
UUB	HH10X15X12	845C	-	69		-		-		-		-
UUB	HH17x30x24	85C	-	15		-		-		-		-
UUB	HH30X48	85C	-	14		-		-		-		-
Wall Box	Wall box	-	-	208		-		-		-		-
						_		_				_

# Equipment

Туре	Specification	FRC	Unit Cost	Quantity	Material Cost (USD)	Labor Cost (USD)	Material Cost	Labor Cost
Fiber Panel	PFP Dist Pnl 288	85C	-	2	-	-	-	-
Fiber Panel	PFP Feeder Pnl 48	85C	-	2	-	-	-	-
Fiber Terminal	EVOLV12100RAW	85C	-	6	-	-	-	-
Fiber Terminal	EVOLV12200RAW	85C	-	1	-	-	-	-
Fiber Terminal	EVOLV12300RAW	85C	-	1	-	-	-	-
Fiber Terminal	EVOLV12400RAW	85C	-	4	-	-	-	-
Fiber Terminal	EVOLV12500RAW	85C	-	2	-	-	-	-
Fiber Terminal	EVOLV121000RAW	85C	-	7	-	-	-	-
ONT	Generic ONT	-	-	208	-	-	-	-
Splice Closure	FOSC450D6	85C	-	7	-	-	-	-
Splice Closure	FOSC450D6	-	-	6	-	-	-	-
Splitter	1X64 Splitter	85C	-	2	-	-	-	-
					-	-	-	-

#### Routes

Туре	Specification FRC	Quantity	Material Cost (USD) L	abor Cost (USD)	Material Cost	Labor Cost
Route (Underground)		40744,97 ft	-	-	-	-
			-	-	-	_

## Conduits

Туре	Specification	FRC	Quantity	Material Cost (USD) Labor Cos	st (USD) Mater	ial Cost Labo	r Cost
Conduit	2" SDR-11 Smooth-Wall Orange	85C	15400,18 ft	-	-	-	-
Conduit	IDUCT 1.25 W TAPE	85C	60,72 ft	-	-	-	-
Conduit	IDUCT 1.25 W TAPE	845C	10918,27 ft	-	-	-	-
				-	-	-	-

### Cables

Туре	Specification	FRC	Quantity	Material Cost (L	JSD) Labor	Cost (USD)	Material C	ost Labor	Cost
Fiber Cable	5B92MT-048	85C	4287,83 ft		-	-		-	-
Fiber Cable	5B92MT-072	85C	1726,63 ft		-	-		-	-
Fiber Cable	5B92MT-144	85C	3343,08 ft		-	-		-	-
Fiber Cable	12F Tail	85C	6739,65 ft		-	-		-	-
Fiber Cable	96F-PFP TAIL	85C	43,10 ft		-	-		-	-
Fiber Cable	288-PFP TAIL	85C	86,21 ft		-	-		-	-
Fiber Cable	Dielectric 216f	85C	3274,76 ft		-	-		-	-
Fiber Cable	Dielectric 288f	85C	1049,35 ft		-	-		-	-
Fiber Cable	FIBERDROP1	845C	49264,00 ft		-	-		-	-
					-	-		-	-