#### Bill of Materials

# Design: PSA-1517PA-BRVLMNYF-CHARLIE

Date: 2/10/2025

Category	Quantity	Material Cost (USD) Labor	Cost (USD) Materia	Cost Lab	or Cost
Structures	330	-	-	-	-
Equipment	248	-	-	-	-
Routes	40744.97 ft	-	-	-	-
Conduits	26379.18 ft	-	-	-	-
Cables	68689.63 ft	-	-	-	-
Total		-	-	-	-

### Structures

Туре	Specification	FRC	Unit Cost	Quantity	Material	Cost (USD)	Labor	Cost (USD)	Material	Cost Labo	or Cost
Cabinet	BJCNDL576-100ST	85C	-	1		-		-		-	-
UUB	HH10X15X12	85C	-	23		-		-		-	-
UUB	HH10X15X12	845C	-	69		-		-		-	-
UUB	HH17x30x24	85C	-	15		-		-		-	-
UUB	HH30X48	85C	-	14		-		-		-	-
Wall Box	Wall box	-	-	208		-		-		-	-
						_		_		_	_

# Equipment

Туре	Specification	FRC	Unit Cost	Quantity	Material Cost (USD)	Labor Cost (USD)	Material Cost	Labor Cost
Fiber Panel	PFP Dist Pnl 288	85C	-	2	-	-	-	-
Fiber Panel	PFP Feeder Pnl 48	85C	-	2	-	-	-	-
Fiber Terminal	EVOLV12100RAW	85C	-	6	-	-	-	-
Fiber Terminal	EVOLV12200RAW	85C	-	1	-	-	-	-
Fiber Terminal	EVOLV12300RAW	85C	-	1	-	-	-	-
Fiber Terminal	EVOLV12400RAW	85C	-	4	-	-	-	-
Fiber Terminal	EVOLV12500RAW	85C	-	2	-	-	-	-
Fiber Terminal	EVOLV121000RAW	85C	-	7	-	-	-	-
ONT	Generic ONT	-	-	208	-	-	-	-
Splice Closure	FOSC450D6	85C	-	7	-	-	-	-
Splice Closure	FOSC450D6	-	-	6	-	-	-	-
Splitter	1X64 Splitter	85C	-	2	-	-	-	-
					-	-	-	-

#### Routes

Туре	Specification FRC	Quantity	Material Cost (USD) L	abor Cost (USD)	Material Cost	Labor Cost
Route (Underground)		40744.97 ft	-	-	-	-
			-	-	-	_

## Conduits

Туре	Specification	FRC	Quantity	Material Cost (USD) Labor Cos	st (USD) Mater	ial Cost Labo	r Cost
Conduit	2" SDR-11 Smooth-Wall Orange	85C	15400.18 ft	-	-	-	-
Conduit	IDUCT 1.25 W TAPE	85C	60.72 ft	-	-	-	-
Conduit	IDUCT 1.25 W TAPE	845C	10918.27 ft	-	-	-	-
				-	-	-	-

## Cables

Туре	Specification	FRC	Quantity	Material Cost (USD) L	abor Cost (USD)	Material Cost	Labor Cost
Fiber Cable	5B92MT-048	85C	4212.83 ft	-	-	-	-
Fiber Cable	5B92MT-072	85C	1551.63 ft	-	-	-	-
Fiber Cable	5B92MT-144	85C	3093.08 ft	-	-	-	-
Fiber Cable	12F Tail	85C	6739.65 ft	-	-	-	-
Fiber Cable	96F-PFP TAIL	85C	18.10 ft	-	-	-	-
Fiber Cable	288-PFP TAIL	85C	36.21 ft	-	-	-	-
Fiber Cable	Dielectric 288f	85C	3774.11 ft	-	-	-	-
Fiber Cable	FIBERDROP1	845C	49264.00 ft	-	-	-	-
				-	-	-	-