#### Bill of Materials

# Design: PSA-1415PA-BRVLMNYF-CHARLIE

Date: 11/18/2024

Category	Quantity	Material Cost (USD) La	bor Cost (USD)	Material Cost	Labor Cost
Structures	351	-	-	-	-
Equipment	263	-	-	-	-
Routes	37501.63 ft	-	-	-	-
Conduits	24397.11 ft	-	-	-	-
Cables	62759.39 ft	-	-	-	-
Total		-	-	-	-

### Structures

Туре	Specification	FRC	Unit Cost	Quantity	Material	Cost (USD)	Labor	Cost (USD)	Material	Cost Lab	or Cost
Cabinet	BJCNDL864-100ST	85C	-	1		-		-		-	-
UUB	HH10X15X12	85C	-	24		-		-		-	-
UUB	HH10X15X12	845C	-	72		-		-		-	-
UUB	HH17x30x24	85C	-	16		-		-		-	-
UUB	HH30X48	85C	-	25		-		-		-	-
Wall Box	Wall box	-	-	213		-		-		-	-
						_		_		-	_

# Equipment

Туре	Specification	FRC	Unit Cost	Quantity	Material Cost (USD)	Labor Cost (USD)	Material Cost	Labor Cost
Fiber Panel	PFP Dist Pnl 432	85C	-	2	-	-	-	-
Fiber Panel	PFP Feeder Pnl 144	85C	-	2	-	-	-	-
Fiber Terminal	EVOLV6100RAW	85C	-	7	-	-	-	-
Fiber Terminal	EVOLV6300RAW	85C	-	1	-	-	-	-
Fiber Terminal	EVOLV6400RAW	85C	-	3	-	-	-	-
Fiber Terminal	EVOLV6500RAW	85C	-	1	-	-	-	-
Fiber Terminal	EVOLV12100RAW	85C	-	9	-	-	-	-
Fiber Terminal	EVOLV12400RAW	85C	-	3	-	-	-	-
Fiber Terminal	EVOLV12500RAW	85C	-	3	-	-	-	-
Fiber Terminal	EVOLV61000RAW	85C	-	1	-	-	-	-
ONT	Generic ONT	-	-	213	-	-	-	-
Splice Closure	FOSC450D6	85C	-	16	-	-	-	-
Splitter	1X64 Splitter	85C	-	2	-	-	-	-
					-	-	-	-

#### Routes

Туре	Specification FF	RC Quantit	y Material Co	ost (USD) Labor Co	st (USD) Materi	ial Cost Labo	r Cost
Route (Underground)		37501.	63 ft	-	-	-	-
				-	-	-	-

## Conduits

Туре	Specification	FRC	Quantity	Material Cost (USD) Labor Cos	st (USD) Materi	al Cost Labo	r Cost
Conduit	2" SDR-11 Smooth-Wall Orange	85C	14637.75 ft	-	-	-	-
Conduit	IDUCT 1.25 W TAPE	845C	9759.36 ft	-	-	-	-
				-	-	-	_

### Cables

Туре	Specification	FRC	Quantity	Material Cost (USD)	Labor Cost (USD)	<b>Material Cost</b>	Labor Cost
Fiber Cable	5B92MT-048	85C	7197.00 ft	-	-	-	
Fiber Cable	5B92MT-072	85C	658.11 ft	-	-	-	-
Fiber Cable	5B92MT-144	85C	4072.53 ft	-	-	-	
Fiber Cable	5B92MT-216	85C	999.99 ft	-	-	-	-
Fiber Cable	6F Tail	85C	2421.35 ft	-	-	-	
Fiber Cable	12F Tail	85C	1971.22 ft	-	-	-	-
Fiber Cable	288-PFP TAIL	85C	11.01 ft	-	-	-	
Fiber Cable	432-PFP TAIL	85C	22.03 ft	-	-	-	-
Fiber Cable	Dielectric 432f	85C	1253.47 ft	-	-	-	
Fiber Cable	FIBERDROP1	845C	44152.67 ft	-	-	-	-
				-	-	-	